# BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

Schedule - B

NAME OF WORK: Improvements to Park Fencing and other works in ward no 12 Shettyhalli Sub Division

| Sl.No | Description of work | Unit | Qty | Approved Rates | |
|---|---|---|---|---|---|
| | | | | In Figures (Rs.) | In Words (Rs.) |
| 1 | 2 | 3 | 4 | 5 | 6 |
| 1 | Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually ( other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables ) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed complete as per specifications and complete as per the direction of Engineer-in-charge of the work. | Cum | 108.00 | 268.92 | Rupees Two Hundred Sixty Eight and Ninety Two Paise Only |
| 2 | Earth work excavation for foundation of building water sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of colds complete as per specifications and complete as per the direction of Engineer-in-charge of the work. | Cum | 83.16 | 322.92 | Rupees Three Hundred Twenty Two and Ninety Two Paise Only |
| 3 | Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms: thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications and complete as per the direction of Engineer-in-charge of the work. | Cum | 11.88 | 5609.52 | Rupees Five Thousand Six Hundred Nine and Fifty Two Paise Only |

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 056

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division.

Scanned by CamScanner

| | | | | | |
|---|---|---|---|---|---|
| 4 | Providing and constructing granite /trap/ baslat size stone masonry in foundation with cement mortar 1:6, stones hammerd dressed in courses not less than 20cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications and complete as per the direction of Engineer-in-charge of the work. | Cum | 39.60 | 4963.68 | Rupees Four Thousand Nine Hundred Sixty Three and Sixty Eight Paise Only |
| 5 | Providing and constructing granite /trap/ baslat size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications and complete as per the direction of Engineer-in-charge of the work. | Cum | 19.80 | 5921.64 | Rupees Five Thousand Nine Hundred Twenty One and Sixty Four Paise Only |
| 6 | Providing ruled pointing to coursed stone masonry with cement mortar 1:3 20mm deep, after raking joints to depth of 20mm necely lining, including cost of materials, labour, curing complete as per specifications and complete as per the direction of Engineer-in-charge of the work. | Sqm | 39.60 | 153.36 | Rupees One Hundred Fifty Three and Thirty Six Paise Only |
| 7 | Filling avaialble excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms in depth compacting each deposited layers by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications and complete as per the direction of Engineer-in-charge of the work. | Cum | 83.16 | 217.08 | Rupees Two Hundred Seventeen and Eight Paise Only |
| 8 | Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting ( excluding cost of earthwork and concrete) complete as per specifications and complete as per the direction of Engineer-in-charge of the work. | Mtr | 90.00 | 910.54 | Rupees Nine Hundred Ten and Fifty Four Paise Only |

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 056

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor,

Scanned by CamScanner

| | | | | | |
|---|---|---|---|---|---|
| 9 | Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint complete as per specifications and complete as per the direction of Engineer-in-charge of the work. | Mtr | 270.00 | 432.48 | Rupees Four Hundred Thirty Two and Forty Eight Paise Only |
| 10 | Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint complete as per specifications and complete as per the direction of Engineer-in-charge of the work. | Sqm | 162.00 | 757.90 | Rupees Seven Hundred Fifty Seven and Ninety Paise Only |
| 11 | Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications and complete as per the direction of Engineer-in-charge of the work. | Cum | 11.12 | 5747.32 | Rupees Five Thousand Seven Hundred Forty Seven and Thirty Two Paise Only |

EXECUTIVE ENGINEER-4
KRIDL, BSMP DIVISION
BENGALURU-560 056

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner